



Auza Contracting

100 S. ...
Phoenix, AZ 85041

Contact: David Auza
Phone: 602-870-6677
Fax: 602-944-0510

Quote To: Steve Garcia
RID
103 W Baseline Rd
Buckeye Az 85326
Phone: 623-386-4719
Fax:
Email: sgarcia@rooseveltirrigation.org

Job Name: RID Channel Demo And shotcrete Replaceme
E of Sante Fe and to about the El mirage Rd a
Proposal Date: 8/31/22
Date of Plans: none
Revision Date:

Thank you for the opportunity to bid this project!

ITEM	DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	AMOUNT
20	GRAVEL TRACK OUT	2.00	EA	2,250.00	4,500.00
30	REMOVE BERM ALONG CANAL/REGRADE BERM AT PERIMETER	6,000.00	LF	1.15	6,900.00
40	REMOVE EXISTING CANAL LINING	144,000.00	SF	1.50	216,000.00
50	REMOVE EXISTING CONCRETE STRUCTURE	1.00	EA	19,000.00	19,000.00
60	REMOVE 1FT OF MATERIAL FROM BOTTOM OF CHANNEL	2,222.00	CY	31.75	70,548.50
70	PLACE 1FT OF ABC MATRL IN THE BOT OF THE CHANNEL	4,100.00	TN	65.50	268,550.00
80	REGRADE SLOPES FOR SHOTCRETE +/- 0.1FT	84,000.00	SF	0.45	37,800.00
90	LOAD AND HAUL OFF MUD MATERIAL TO LANDFILL	2,222.00	CY	36.80	81,769.60
100	REGRADE ACCESS ROAD CLEAN UP	1.00	LS	6,200.00	6,200.00
200	ALT: 1SACK ABC SLURRY BACKFILL IF NEEDED	1.00	CY	255.00	255.00
910	Mobilization	1.00	EA	21,000.00	21,000.00
GRAND TOTAL					\$732,523.10

NOTES:

INCLUSIONS:

- Dust control per Maricopa County requirements.
- Payment terms per Arizona prompt payment statute.
- Existing Shotcrete and structure removals and disposal.
- Channel bottom 1ft over exc. Replace with 1ft of ABC recompacted
- Regrade/clean up slopes for shotcrete placement
- Remove existing berm along the channel edge and install new berm on adjacent edge of road to prevent water runoff from mud excavation.
- Replace berm along channel edge and clean up roads after mud haul off.

Final billing will be based on field measured quantities. Length of channel worked on.
Added an ABC ALT installed to repair "pumping or excess muddy areas that cant be fixed in a timely manner. This will be paid on cy's installed and tickets from the supplier.
Gravel Track outs
Light plants if needed.

EXCLUSIONS:

Bonds, Sales tax, permit fees, inspection fees, surveying, engineering and testing fees.
NPDES, SWPPP, erosion control and related items.
Relocation of existing utilities due to conflicts.
Traffic control, barricades, or officers.
Additional mud removal deeper than 1 foot. Unless agreed upon by owner to do so.
Pumping of water. All water should be drained from the water release point at the river bottom.
Home owner notifications of work going on during the dry up if works runs into the night or on weekends.

Miscellaneous Notes

Approved by Name/Title/Date.....